



IMPORTANT

Pay close attention to the end of line DIP switch settings in the diagram and make sure you match them in the installation.

All in line monitors should be set with both switches **"OFF"**.

End of the riser monitor will have either 1 or both switches **"ON"**

IMPORTANT

Pay close attention to the end of line jumper settings in the diagram and make sure you match them in the installation.

All in line 6925/6925.1 should be set in the **"A"**.

The end of the line 6925/6925.1 should be set to **"B or C"**

